

Casement Frames

STANDARD MANUFACTURING CONSTRUCTION DETAILS

- Three Sided Frame Construction
- 14, 12, 10 gauge Stainless Steel
- 1/4" Stainless Plate
- Alloy 304, 304L, 316, 316L
- Finish #4 Satin (*standard)
- Grain Long Direction Of Each Piece (*standard)
- Mitered Corners (*standard)
- Knock-Down Construction (*standard)
- Face Fully Welded (*optional)
- Hole Prep available for bolt-in installation

**See Options or Consult with Factory
for Other Applications*

Jamb/Head Details

